

Trade Scopes

SBDI

Saskatchewan Bid Depository Inc.

contactus@sbdi.ca

www.sbdi.ca

REBAR SCOPE

Page 1 of 2

Revised 2001

A tender to supply only F.O.B. truck at jobsite, or supply and place where noted on tender, rebar and welded wire mesh shall include only those items from the following list which clearly are indicated to be required by the plans and specifications available at time bids are requested.

On supply only tenders, this contractor shall include the following items regardless of where they may appear in the tender documents unless specifically noted otherwise in this scope.

INCLUDED:

1. Epoxy coated rebar and patch kit.
2. Fabrication of bars; this shall include smooth rods for joints, cut, bent, bundled and tagged or color-coded.
3. Prime cost sums and/or contingency funds when a specific dollar amount is listed in the specifications pertaining to this work.
4. Preparation of placing drawings and barlists.
5. Supply reinforcing steel for concrete filled masonry and du-al and similar type blocks.
6. Supply of welded wire mesh or structural wire fabric in flat sheets or rolls.
7. Support and/or spacer bars when specified or specifically shown on the drawings.

EXCLUDED:

Temporary heat, light, power (up to a maximum of 120/208 volts and an adequate amperage for temporary lighting, heating and convenience outlets, sanitation) or as specified.

1. Accessories for masonry or du-al or similar type blocks.
2. Inspection or testing.
3. Placing, placing accessories and tie wire.
4. Post-tensioning cables, anchorage zone reinforcement and post-tensioning supports.
5. Reinforcing steel used in piles.
6. Supply of pile dowels.
7. Dowels to precast.
8. Caldwell welds and burrard couplers.
9. Mechanical and exothermic couplers.
10. Inserts and adhesive anchors.
11. Any bolts and washers.

When fabricator places rebar and welded wire mesh, they shall:

INCLUDE:

1. Placing accessories, tie wire, cadwelds and burrard couplings.
2. Clean up.
3. Unloading.

Trade Scopes

SBDI

Saskatchewan Bid Depository Inc.

contactus@sbdi.ca

www.sbdi.ca

REBAR SCOPE

Page 2 of 2

EXCLUDE:

1. Temporary heat, light, power and sanitation.
2. Water.
3. Hoarding.
4. Hoisting.
5. Pile rebar.
6. Greasing and placing of smooth dowels.
7. Placing of masonry rebar.
8. Placing of sidewalk and curbs. (Trade will provide an approximate quantity take-off of reinforcing and welded wire mesh for evaluation of installation costs only.)
9. Placing of dowels from slabs or beams to precast or masonry.
10. Placing of post-tensioning cable, anchorage zones reinforcement and post-tensioning supports.

NOTE: Post tensioning cables, accessories, and supports are not part of this scope.